

APPENDIX 2
ACCESS ROAD CULVERT DESIGN

Chkd. by _____ Date _____

Engineers & Scientists

Sheet No. 1 of 13

Subject HAULAGEWAY CULVERT SIZING

METHOD: RATIONAL $Q = CIA$ SOURCES: ① "TIME OF CONCENTRATION OF SMALL DRAINAGE BASINS" p 362
Kirpich, Civil Engineering, Vol 10, No 6, June 1940

② "RAINFALL INTENSITY CHARTS" BINGHAMPTON, NY

③ HYDRAULIC CHARTS FOR THE SELECTION OF HIGHWAY
CULVERTS Bureau of Public Roads, Hydraulic Engineering
Circular No 5, 1965.④ DESIGN CHARTS FOR OPEN CHANNEL FLOW Federal
Highway Administration, Hydraulic Design Series No 3,
1973.

⑤ ARCHITECTURAL STANDARDS

Assumed C values:

WOODED	0.15
RESIDENTIAL	0.35
BRUSH	0.35
PAVEMENT	0.95

STORM FREQUENCY : 25 YR

1A/13



$$1 \text{ IN}^2 = 250,000 \text{ SF}$$

AREA	READINGS IN ²	SF	ACRL
A	.082 .082 > .082	20,500	.47
B	.287 .302 > .287 .272	71,750	1.65
C	.157 .152 > .152 .152	38,000	.87
D	.055 > .056 .057	14,000	.32
E	.362 .355 > .359 .360	89,750	2.06

AREA A

$$A = .47 \text{ Ac dense Brush}$$

$$C = .35$$

$$I: H = 700 - 680 = 20 \quad L = 300' \quad T_c = \frac{1.3}{2} \times 2 = 4 \text{ min}$$

$$I = 7.0$$

$$Q = (.35)(7.0)(.47) = 1.15 \text{ cfs} \checkmark$$

12" CMP. 30' @ 1.0%

AREA A USE 12" MITER
CMP

AREA B

$$A = 1.65$$

$$C = \frac{(.33)(.35) + (.67)(.15)}{1} = 0.22$$

$$I: H = 680 - 635 = 45 \quad L = 550' \quad T_c = 3.6 \times 2 = 7.2 \text{ min}$$

$$I = 6.3$$

$$Q = (.22)(6.3)(1.65) = 2.3 \text{ cfs} \checkmark$$

31'-15" CMP @ 1.0%

AREA B USE 15"
CMP
MITERED

AREA C

$$A = .32$$

$$C = .15$$

$$I: H = 640 - 625 = 35 \quad L = 280 \quad T_c = 1.5 \times 2 = 3 \text{ min}$$

$$I = 7.0$$

$$Q = (.15)(.32)(7.0) = .34 \text{ cfs} \checkmark \text{ from Area A use 12" CMP MITERED}$$

AREA D (combined E+D - grade road ditch)

$$A = 2.06 + .32 = 2.38$$

$$C = .25(.35) + .70(0.15) + .05(.15) = .24$$


$$I: H = 635 - 597 = 38 \quad L = 750 \quad T_c = 5'$$

$$I = 7.0$$

$$Q = (.24)(7.0)(2.38) = 4 \text{ cfs} \checkmark$$

TIME OF CONCENTRATION OF SMALL DRAINAGE BASINS

8/13



- Note: 1) Use nomograph T_c for natural basins with well defined channels, for overland flow on bare earth, and for mowed grass roadside channels.
- 2) For overland flow, grassed surfaces, multiply T_c by 2.
- 3) for overland flow, concrete or asphalt surfaces, multiply T_c by 0.4.
- 4) For concrete channels, multiply T_c by 0.2.

Reference: Based on study by P.Z.Kirpich, Civil Engineering,
 Vol. 10, No. 6. June 1940. p. 362.



9/13

3 4 5 6 8 10 12 18 24
HOURS

10 15 20 30 40 50 60 2 3 4 5 6 8 10 12 18 24
MINUTES DURATION HOURS

IK

BINGHAMTON, NEW YORK
1905-1954




255
125
125
5:0
3:5
3:1

30

~ 11.3


25 YR STORM

10/13




HEADWATER DEPTH FOR C. M. PIPE CULVERTS WITH INLET CONTROL


BUREAU OF PUBLIC ROADS JAN. 1963



12/13



PIPE FLOW CHART
15-INCH DIAMETER



PIPE FLOW CHART
18-INCH DIAMETER

APPENDIX 3
EROSION AND SEDIMENT CONTROL DESIGN

SCALE 1" = 100' SF/SI = 10,000

FROM 100 SCALE	PHASE	SI	AUESI	SF	AC
	I	44.3 44.66	44.48	444800	10.2
	II	10.06 9.85 10.03	9.98	99,800	2.3
	III	7.7 7.6	7.65	76,500	1.8
	IV	7.9 7.94	7.92	79,200	1.8
	V	45.55 45.57	45.56	455,600	10.4
	ALL	79.32 79.08 79.11	79.17	791,700	18.2

100 SCALE PHOTOCOPY	OFF-SITE DRAINAGE	SI	AUE	SF	AC
	PH I	2.47 2.52 2.50	2.5	25000	.57
	PH II	3.67 3.09 3.04	3.67	36700	.84

200 SCALE	AREA CHANGED FLOW PATTERN	SI	AUE	SF	AC
		2.9 2.96 2.90	2.96	118400	2.72

A. PURPOSE TO SIZE STRUCTURES TO DIVERT STORM WATER AWAY FROM ACTIVE WINE AREAS

PARAMETERS:

SHALEY SILT LOAM SOIL
 AGRICULTURAL LAND
 SEED, TEMPORARY MIX
 DIVERSION WILL BE MAINTAINED
 DISCHARGE TO STABLE, VEGETATED AREA

DESIGN STORM = 25 YRS
 REQD FREEBOARD = 0.3' } PC 4.2.2
 VELOCITY MAY 2.0 FPS @ RET D+E
 C factor = .30 WOODED W/ ROCK OUTCROPS
 steep meadow

B. DIVERSION ABOVE PHASE I

$$Q = C I A$$

$$A = .57 AC$$

$$C = \text{WOODED} = .30$$

$$I: L = 170' \quad H = 790 - 770 = 20' \quad T_c = 1 \times 2 = 2$$

$$F = 7.0$$

$$Q = (.3)(7)(.57) = 1.2 \text{ cfs} \leq 5 \text{ cfs}$$

USE SMALL DIVERSION SPECS 4.2.2

C. DIVERSION ABOVE PH. II

$$Q = C I A$$

$$A = .84$$

$$C = \text{WOODED} = .30$$

$$I: L = 300' \quad H = 830 - 805 = 25' \quad T_c = 1.6 \times 2 = 3.2$$

$$I = 7$$

$$Q = (.3)(7)(.84) = 1.76 \text{ cfs} \leq 5 \text{ USE SMALL}$$

DIVERSION SPECS

D. DIVERSION ABOVE PH III

$$Q = C I A$$

$$A = 2.3$$

$$C = .3$$

$$I = 180' \quad H = 805 - 760 = 45' \quad T_c = 1.0 \times 2 = 2$$

$$I = 7$$

$$Q = (.3)(7)(2.3) = 4.8 \text{ cfs} \leq 5 \text{ cfs USE SMALL}$$

DIVERSION SPECS

E. DIVERSION ABOVE IV

$$Q = C I A$$

$$A = 1.8$$

$$C = .3$$

$$I = \text{MINIMUM} = 7$$

$$Q = (.3)(7)(1.8) = 3.8 \leq 5 \text{ cfs USE SMALL}$$

DIVERSION SPECS

F. DIVERSION ABOVE V

$$Q = C I A$$

$$A = 1.8$$

$$C = .3$$

$$I = 7$$

$$Q = (.3)(7)(1.8) = 3.8 \leq 5 \text{ cfs}$$

E. STONE OUTLET DIMENSIONS

$$L = 6 \times \text{CONTRIBUTING ACRES}$$


$$\text{MAX CONT. AREA} = 2.3 \text{ AC}$$

$$L = 6 \times 2.3 = 13.8'$$

USE 14'

SMALL DRAINAGE BASINS

4/9




- Note: 1) Use nomograph T_c for natural basins with well defined channels, for overland flow on bare earth, and for mowed grass roadside channels.
- 2) For overland flow, grassed surfaces, multiply T_c by 2.
- 3) for overland flow, concrete or asphalt surfaces, multiply T_c by 0.4.
- 4) For concrete channels, multiply T_c by 0.2.


Reference: Based on study by P.Z.Kirpich, Civil Engineering,
 Vol. 10, No. 6. June 1940. p. 362.

RAINFALL INTENSITY-DURATION-FREQUENCY CURVES


ROSWELL, NEW MEXICO
1903-1990




SANTA FE, NEW MEXICO
1903-1927, 1929-1940



ALBANY, NEW YORK
1903-1954



BINGHAMTON, NEW YORK
1903-1934



DI- TY	TYPICAL AREA OF PROTECTION	DESIGN STU- FREQUENCY	FREEBOARD REQUIRED
Permanent	Agricultural Land	25 years	0.3 ft.
	Urban Land Areas, Play Fields, Recreation Areas, Agricultural Buildings, etc.	25 years	0.3 ft.
	Homes, schools, Industrial buildings, etc.	50 years	0.5 ft.



Small Diversions

1. Where the diversion channel grade is between 0.25% and 5%, a permanent vegetative cover is planned and the design flow is equal to or less than given below, the dimensions given below for a parabolic channel may be used instead of preparing an individual design for the diversion.

CHANNEL DIMENSIONS		
Q (cfs)	TOP WIDTH (ft.)	DEPTH (ft.)
5	12	1.9
10	22	1.9

The depth given above includes 0.3 ft. freeboard and 0.1 ft. settlement. Side slopes shall be 3:1 or flatter, and the ridge top width shall be 4 ft. or wider.

2. Where the diversion will be a temporary diversion to direct water off a graded right of way onto stable areas and the only area draining toward the diversion is the right of way; the following spacings, and the size given above for 5 cfs may be used instead of preparing individual designs for each diversion.

ROAD GRADE (percent)	APPROXIMATE DISTANCE BETWEEN DIVERSIONS (ft.)
1	400
2	245
5	125
10	78
15	58
20	47
25	40
30	35

Velocity

The maximum permissible velocity for design flow will be determined by the most erodible soil texture exposed and the type of vegetation expected and maintained in the channel. The following table will be used in selecting maximum permissible velocities:

1/9

Protection Against Sedimentation

When the movement of sediment into the diversion channel is a significant problem:

1. Land treatment or structural measures shall be installed to stabilize the source of sediment or trap the sediment.
2. If it is not possible to stabilize or trap the sediment, a filter strip of close growing grass shall be maintained above the diversion channel. The filter strip width measured from the center of the channel shall be at least one-half the channel top width plus 15 feet.

Outlet

Each diversion must have an adequate, stable outlet. The outlet may be: a grassed, stone centered, or lined waterway; a vegetated or paved area; a grade stabilization structure; a storm sewer; a stable watercourse; a tile outlet; or open channel.

The outlet, in all cases, must be stable and convey water to a disposal point where damage will not result. Constructed vegetative outlets must be established prior to diversion construction.

Temporary Stone Outlet Structure

A temporary stone outlet structure for a diversion may be used only where the contributing watershed is less than five acres. The minimum length, in feet, of the crest of the stone outlet structure shall be equal to six times the number of acres of the contributing drainage area. The crest of the stone outlet structure shall be level and at least six inches lower than the lowest elevation of the top of the diversion. The stone shall be crushed stone and be 4" to 8" in diameter except for a one-foot thick blanket of 2" diameter stone on the upstream face.

The temporary stone outlet structure shall be located so as to discharge onto an already stabilized area or into a stable watercourse. The stone structure shall be embedded into the soil a minimum of four inches.

Permanent Cover and Erosion Protection

A permanent vegetative cover shall be established on all diversions in accordance with the Standards for Permanent Vegetative Cover for Soil Stabilization, p. 3.2.1 or Standards for Permanent Stabilization with Sod, p. 3.4.1. Where the season and other conditions may not be suitable for growing permanent erosion resistant cover, erosion protection will be provided in accordance with the Standards for Temporary Vegetative Cover for Soil Stabilization, p. 3.1.1 or Standards for Stabilization with Mulch Only, p. 3.3.1.

Diversions that are not designed to have a permanent vegetative cover shall be designed for bare channel velocities and with flat side slopes to prevent channel and side slope erosion. Diversions that are designed to have a permanent vegetative cover shall be seeded from the toe of the backslope to the upstream side of the designed channel width plus any required filter strip. Other areas disturbed by diversion construction shall also be seeded.

Installation Requirements

All trees, brush, stumps, or other objectionable material shall be removed so they will not interfere with construction or proper functioning of the diversion. All ditches or gullies which must be crossed will be filled and compacted prior to or as part of the construction. Fence rows and other obstructions that will interfere with construction or the successful operation of the diversion are to be removed.

Vegetation is to be removed and the base for the ridge thoroughly disked before placement of fill.

The minimum constructed cross-section is to meet the design requirements.

The top of the constructed ridge is not to be lower than the design elevation plus the specified amount for settlement.

Fertilizing, seeding, and mulching shall conform to the requirements in the Standards for Permanent Vegetative Cover for Soil Stabilization, p. 3.2.1.

If there is no sediment protection provided on temporary diversions, it should be anticipated that periodic cleanout may be required.

Construction operations shall be carried out in such a manner that erosion and air and water pollution will be minimized. State and local laws shall be complied with.

APPENDIX 4
BLASTING

Subject: _____

A. BLASTING HAS BEEN OCCURRING ALTERNATE SATURDAY
 BLASTING LOCATED $\approx 700'$ FROM EXISTING BLDGS.

B. DISTANCE TO EXISTING BUILDINGS / STRUCTURES FOR
 PROPOSED BLASTING
 LINGS RD $\approx 400'$
 POWER LINES $\approx 700'$

C. PEAK PARTICLE VELOCITY LIMITS (MAX) FOR GROUND
 VIBRATIONS WHEN DISTANCE FROM BLASTING SITE
 = 301 - 5000' \Rightarrow 1.00 inch/sec

D. SCALE DISTANCE EQUATION WHEN DISTANCE
 FROM BLASTING SITE = 301 - 5000'

$$W = \left(\frac{D}{55} \right)^2$$

W = max weight of
 explosives that can be
 detonated w/ 8 millise

D = distance to site

$$W = \left(\frac{400}{55} \right)^2 = 53 \#$$